

Wayfinding and Signage Standards

Revision 12
14 December 2023

Chapter G.3 (Sections 13 - 17)

For sections 01 - 08, refer to chapter G.1
For sections 09 - 12, refer to chapter G.2
For sections 18 - 23, refer to chapter G.4



UNSW
SYDNEY

Contents

13: Operational Series – Page 305

- OP.01 Help Point ID Family
- OP.02 General ID Family
- OP.03 Utility ID Family
- OP.04 Drop Box ID Family
- OP.05 Water Refill
- OP.06 Waste Bins
- OP.07 Rules of Use Family

14: Statutory Series – Page 323

- ST.01 Amenity: Braille and Tactile
- ST.02 Door Mounted Family
- ST.03 Fire Extinguisher & FHR Family
- ST.04 Regulations Family
- ST.05 Security Warning Family
- ST.06 Hazard & Danger Notices Family
- ST.07 Safety Decal
- ST.08 Exit Signage Family

15: Temporary & Display Series – Page 348

- TD.01 Notice Boards: External Large
- TD.02 Notice Boards: External Small
- TD.03 Notice Boards: Internal Large
- TD.04 Notice Boards: Internal Small
- TD.05 Notice Boards: Digital
- TD.06 A3 & A4 Display Family
- TD.07 Temporary Sign
- TD.08 Construction Hoarding

16: Environmental Graphics – Page 365

- EG.01 Privacy Graphics
- EG.02 Security Booth Graphics

17: Specialty Series – Page 377

- The Chancellery
- Celebrating Women Project
- Alumni Park Artwork
- Morven Brown Student Space Identity
- Foosball Tables
- Business School

Section

13.0

Operational Series

This section documents all the operational signs of the system including specifications for both external and internal signs.

OP.01 Help Point ID Family

OP.02 General ID Family


OP.03 Utility ID Family

OP.04 Drop Box ID Family


OP.05 Water Refill

OP.06 Waste ID


OP.07 Rules of Use Family



OP.01a
Front & Side Elevation
Freestanding totem
Scale 1:25



OP.01b
Front Elevation
Wall-mounted sign
Scale 1:25





OP.01c
Front Elevation
Cantilevered sign
Scale 1:25

Sign Location

Purpose
Identifies help point locations. Refer to Section 3, Addressing & Terminology, Category 10

Location
Located above (cantilevered sign) or integrated with (freestanding and wall mounted signs) nominated Help Point intercoms.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Addressing & Terminology
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Detail
Scale 1:2

Detail
Scale 1:10

Graphic Layout

Pictogram
300mm diameter

Messaging
FS Millbank Regular
Alignment: Centre
Size/ Leading: 7mm, 8mm
Tracking: 10+, Optical kerning

UNSW logo
50mm height

Back
Double sided, content to be repeated on both sides of signform


Construction & Materials

Materiality Legend


- A1**
 - A1 finish for illumination
- S1**
 - S1 print to opal acrylic
- V3**
 - V3 print applied on top of aluminium
- C5**
 - Painted to match PMS 165C Safety Orange with satin finish

Construction Details

- Refer to: Section 8, Construction Standards, Totem Signforms



Detail
Scale 1:5



Detail
Scale 1:2

Graphic Layout

Pictogram
300mm diameter

Messaging
FS Millbank Regular
Alignment: Centre
Size/ Leading: 7mm, 8mm
Tracking: 10+, Optical kerning

UNSW logo
50mm height


Construction & Materials

Materiality Legend

- A1**
 - A1 finish for illumination
- S1**
 - S1 print to opal acrylic
- V3**
 - V3 print applied on top of aluminium
- C5**
 - Painted to match PMS 165C Safety Orange with satin finish

Construction Details

- Refer to: Section 8, Construction Standards, Wall Mounted Signforms, and Cantilevered Signforms



Detail
Scale 1:4

Graphic Layout

Pictogram
300mm diameter

Messaging
FS Millbank Regular
Alignment: Centre
Size/ Leading: 7mm, 8mm
Tracking: 10+, Optical kerning

UNSW logo
50mm height


Back
Double sided, content to be repeated on both sides of signform

Construction & Materials


Materiality Legend

- | | | |
|---|--|--|
| <div>C5</div> <ul style="list-style-type: none">Painted to match PMS 165C Safety Orange with satin finish | <div>S1</div> <ul style="list-style-type: none">S1 print to opal acrylic | <div>V3</div> <ul style="list-style-type: none">V3 print applied on top of aluminium |
|---|--|--|


Construction Details
Refer to: Section 8, Construction Standards, Wall Mounted Signforms, and Cantilevered Signforms




Facility Utilities
100mm above utility location
Scale 1:25




Authorised Access
100mm above fob reader
Scale 1:25



Push/ Pull Door
50mm above door handle/knob
Scale 1:25



Seating Capacity
300mm from door entry
Scale 1:25




CATS Room Signage
Top of sign at 1600mm FFL
Scale 1:25

Sign Location


Purpose
Provide operational/ regulatory information at designated area.

Location
Applied on solid wall or glazing were appropriate


- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance




OP.02a
Facility Utilities
Scale 1:2




OP.02b
Authorised Access
Scale 1:2



OP.02c
Seating Capacity
Scale 1:2



OP.02d
Push Door
Scale 1:2



OP.02e
Pull Door
Scale 1:2

Graphic Layout

Type Style 1 (Typical Messaging)

FS Millbank Regular
Size/ Leading: 10mm, 5mm

Type Style 3 (Major numbers or codes)

FS Millbank Regular
Size: 20mm

Type Style 4 (Footer Messaging)

FS Millbank Regular
Size/ Leading: 5mm, 5mm

Alignment

Left

Tracking

10+, Optical kerning


Construction & Materials

Materiality Legend

- | | |
|------------------------------|--------------------------|
| C1 | V2 |
| • C1 finish on 3mm aluminium | • V2 on top of aluminium |

Construction Details

- Refer to: Section 8, Construction Standards, Wall Mounted Signforms




Graphic Layout


- Header Messaging**
FS Millbank Regular
Size: 15mm, 25mm
- Secondary Messaging**
FS Millbank Regular
Size/ Leading: 8mm, 6mm
- Alignment**
Left
- Tracking**
10+, Optical kerning
- Furniture Configuration Diagram**
To be provided by UNSW and sized to signform

Construction & Materials


- Materiality Legend**
- | | | |
|------------------------------|--------------------------|--|
| C1 | V2 | V3 |
| • C1 finish on 3mm aluminium | • V2 on top of aluminium | • V3 print applied on top of aluminium |
- Construction Details**
- Refer to: Section 8, Construction Standards, Wall Mounted Signforms




Elevation
Scale: 1:25




Location 01 -
Full height cupboard
Scale 1:5



Location 02 -
Overhead cupboard
Scale 1:5



Location 03 -
Bins inside joinery
Scale 1:5




Location 04 -
Drawer
Scale 1:5

Sign Location


Purpose
Identifies staff/ students utilities at kitchenettes, stationery rooms and print areas.

Location
Applied on solid wall, glazing, cupboard leaf or drawer front were appropriate


- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



OP.03a
General Recycling Detail
Scale 1:1



OP.03b
Paper Recycling




OP.03c
Organics



OP.03d
General Waste



OP.03e
Fridge




OP.03f
Cutlery



OP.03g
Crockery



OP.03h
Cups & Mugs



OP.03i
First Aid

Graphic Layout

Utility ID
Pictogram: 30mm height
Refer to Section 9, Graphic Standards, Pictogram Suite

Construction & Materials

Materiality Legend

- C1


 - C1 finish on 3mm aluminium
- V2

 - V2 on top of aluminium
- V3

 - Print to V3 on top of aluminium to match PMS 348U


Construction Details

- Refer to: Section 8, Construction Standards, Wall Mounted Signforms



After Hours Return
Integrated into utility
Scale 1:25

Note
Drop box shown is indicative only.



Assignment Drop-off
50mm above slot
Scale 1:25


Note
Drop box shown is indicative only.

Sign Location


Purpose
Identifies student drop boxes

Location
Applied on solid wall, glazing, cupboard leaf or drawer front were appropriate.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



OP.04a
After Hours Return
Scale 1:4



OP.04b
Assignment Drop-off
Scale 1:4

Graphic Layout

Messaging
FS Millbank Regular
Size/ Leading: 30mm, 20mm
Alignment: Left
Tracking: 10+, Optical kerning

Construction & Materials

Materiality Legend


- C1

 - C1 finish on 3mm aluminium
- V2

 - V2 on top of aluminium

Construction Details

- Refer to: Section 8, Construction Standards, Wall Mounted Signforms





Sign Location

Purpose
Identifies water refill station

Location
Integrated with water refill station

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Graphic Layout

Location ID
FS Millbank Bold
Size/ Leading: 30mm, 15mm

Header Messaging
FS Millbank Bold
Size/ Leading: 45mm, 30mm

Body Messaging
FS Millbank Bold & Regular
Size/ Leading: 30mm, 15mm


Alignment
Left

Tracking
10+, Optical kerning

Construction & Materials

Materiality Legend

- | | | |
|------------------------------|--------------------------|--|
| C1 | V2 | V3 |
| • C1 finish on 3mm aluminium | • V2 on top of aluminium | • V3 print applied on top of aluminium |




Typical Elevation
1:20

Sign Location

Purpose
Identifies waste bin unit and what types of waste are and are not to be disposed of

Location
Applied on front face of campus bins.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Graphic Layout

Mixed Waste ID
FS Millbank Bold
Alignment: Left
Size/ Leading: 30mm, 15mm
Kerning: 10+, Optical kerning

Messaging
FS Millbank Bold
Alignment: Left
Size/ Leading: 9mm, 6mm
Tracking: 10+, Optical kerning


Pictogram
75mm diameter

Construction & Materials

- Materiality Legend**
- | | |
|------------------------------|--|
| C2 | V3 |
| • C1 finish on 3mm aluminium | • V3 print applied on top of aluminium |

Construction Details

- Refer to: Section 8, Construction Standards, Wall Mounted Signforms




Sign Location


Purpose
Provides rules of use and other relevant information for outdoor sporting facilities

Location
Mounted to fences or poles adjacent to sporting facility areas

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Template 01 - Rules of Use
1:4



Template 02 - Information
1:4

Graphic Layout

Header Messaging
FS Millbank Bold
Alignment: Left
Size/ Leading: 20mm, 15mm
Kerning: 10+, Optical kerning

Body Messaging
FS Millbank Bold / Regular
Alignment: Left
Size/ Leading: 10mm, 6mm
Tracking: 10+, Optical kerning

Rules of Use
FS Millbank Regular
Alignment: Left
Size/ Leading: 8mm, 6mm
Tracking: 10+, Optical kerning

Construction & Materials

Materiality Legend

- | | | |
|------------------------------|--------------------------|--|
| C1 | V2 | V3 |
| • C1 finish on 3mm aluminium | • V2 on top of aluminium | • V3 print applied on top of aluminium |

Construction Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms


Section

14.0


Statutory Series

This section documents all the statutory signs of the system including specifications for both external and internal signs.

ST.01 Amenity Braille & Tactile Family
ST.02 Door Mounted Family
ST.03 Fire Extinguisher & FHR Family
ST.04 Regulations Family
ST.05 Security Warning Family
ST.06 Hazard & Danger Notices Family
ST.07 Safety Decal
ST.08 Exit Signage Family



Elevation
Scale 1:20



Elevation
Scale 1:20

Sign Location

Purpose
Provide operational/regulatory information at designated area. Refer to Section 3, Addressing & Terminology, Category 11.


Location
At main entry to toilet facility. To be applied to solid wall on latch side of door.

Alternate Location
Alternate location centre aligned on door, only to be used when no wall space is available on latch-side primary location.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance

Section 14 – Amenity Braille & Tactile Family

ST.01



Typical Graphic Layouts

Pictogram

80mm height

Messaging

Arial

Alignment: Left


Size/ Leading: 15mm, 10mm

Tracking: 10+, Optical kerning

Braille

Message content as illustrated by tactile text and as required by code, braille must be located 8mm below the bottom line of text (not including descenders).

Braille locator must be used if there are multiple lines of text and characters, horizontally aligned with the first line of braille text.



Construction & Materials

Materiality Legend

- | | | |
|------------------------------|------------------------------|--|
| C1 | C2 | |
| • C1 finish on 3mm aluminium | • C2 finish on 3mm aluminium | |
| 01 | 02 | 03 |
| • Tactile to match C2 finish | • Braille to match C1 finish | • Tactile to match AS 2700 Ultramarine B21 |

Fixing Details

- Refer to: Section 8, Construction Standards, Wall Mounted Signforms

Page 2 of 4

Units: mm

Section 14 – Amenity Braille & Tactile Family – Dark Wall/Door Application

ST.01a




ST.01a - Male Toilet
Scale 1:5



ST.01b - Female Toilet
Scale 1:5



ST.01c - Male Ambulant Toilet
Scale 1:5



ST.01d - Female Ambulant Toilet
Scale 1:5



ST.01e - Parent Room
Scale 1:5



ST.01f - Accessible RH Toilet
Scale 1:5



ST.01g - Accessible LH Toilet
Scale 1:5



ST.01h - Male Showers
Scale 1:5



ST.01i - Female Showers
Scale 1:5



ST.01j - All Genders Toilet
Scale 1:5



ST.01k - All Genders Toilet
Scale 1:5



ST.01l - All Genders Toilet
Scale 1:5



ST.01m - All Genders Accessible Toilet RH
Scale 1:5



ST.01n - All Genders Accessible Toilet LH
Scale 1:5




ST.01o - Parent Room
Scale 1:5



ST.01p - Parent Room
Scale 1:5



ST.01q - Shower
Scale 1:5



Additional amenity signs may be set using layouts provided, to be set on a site-by-site basis.

Typical Graphic Layout

Pictogram
70mm height

Messaging
Arial
Alignment: Left
Size/ Leading: 15mm, 10mm
Tracking: 10+, Optical kerning

Braille
Message content as illustrated by tactile text and as required by code, braille must be located 8mm below the bottom line of text (not including descenders).
Braille locator must be used if there are multiple lines of text and characters, horizontally aligned with the first line of braille text.

Colourway
Colourway of sign to be selected based on wall/door surface, to meet contrast luminance requirements in accordance with:


Signs and graphics for disability access:
AS 1428.1 and AS 1428.2.
Braille & Tactile wayfinding signs:
AS 1428.1 and NCC S15C2 (2019: Spec D3.6:2).




ST.01a - Male Toilet
Scale 1:5



ST.01b - Female Toilet
Scale 1:5



ST.01c - Male Ambulant Toilet
Scale 1:5



ST.01d - Female Ambulant Toilet
Scale 1:5



ST.01e - Parent Room
Scale 1:5



ST.01f - Accessible RH Toilet
Scale 1:5



ST.01g - Accessible LH Toilet
Scale 1:5



ST.01h - Male Showers
Scale 1:5



ST.01i - Female Showers
Scale 1:5



ST.01j - All Genders Toilet
Scale 1:5



ST.01k - All Genders Toilet
Scale 1:5



ST.01l - All Genders Toilet
Scale 1:5



ST.01m - All Genders Accessible Toilet RH
Scale 1:5



ST.01n - All Genders Accessible Toilet LH
Scale 1:5



ST.01o - Parent Room
Scale 1:5



ST.01p - Parent Room
Scale 1:5



ST.01q - Shower
Scale 1:5



Additional amenity signs may be set using layouts provided, to be set on a site-by-site basis.

Variants

Pictogram
80mm height

Messaging
Arial
Alignment: Left
Size/ Leading: 15mm, 10mm
Tracking: 10+, Optical kerning


Braille
Message content as illustrated by tactile text and as required by code, braille must be located 8mm below the bottom line of text (not including descenders).

Braille locator must be used if there are multiple lines of text and characters, horizontally aligned with the first line of braille text.


Colourway
5mm black border to be added to sign based on wall/ door surface requirements, to meet contrast luminance in accordance with:

Signs and graphics for disability access:
AS 1428.1 and AS 1428.2.

Braille & Tactile wayfinding signs:
AS 1428.1 and NCC S15C2 (2019: Spec D3.6:2).



Elevation - Standard door panel
Scale: 1:25



Elevation - Double door panel
Sign to be placed on active leaf
Scale: 1:25

Sign Location

Purpose

Identify room and/or cupboard functions for BOH destinations to meet statutory regulations. Refer to Section 3, Addressing & Terminology, Category 11.


Location

For statutory room and/or cupboard signs, to be applied to front of solid doors, on latch-side and/or both doors as required.

For Exit operational instructions (Offences Relating to Fire Exits) to be located as required by Clause 183 of NSW Environmental Planning & Assessment Regulation 2000. To be installed in a conspicuous position adjacent to a door way providing access to (but not within) a fire isolated stairway, passageway or ramp. Underside of panel to align with underside of adjacent room identification panel, set out as indicated adjacent.

Note


- For sign type selection, refer to: Section 5, The Process, Step 3
- For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
- For sign maintenance, refer to: Section 21, Maintenance



ST.02a
Two Line Messaging
Scale 1:5



ST.02b
Three Line Messaging
Scale 1:5



Contrast Luminance
5mm black border to be added to sign to meet BCA contrast luminance requirements.

ST.02c
Exit Level
Scale 1:2

Note
Exit Level (xx) font to be Arial.

Graphic Layout

Messaging
FS Millbank Bold
Alignment: Left
Size/ Leading: 20mm, 10mm
Tracking: 10+, Optical kerning

Dividing Line
Line weight: 1mm


Braille
Message content as illustrated by tactile text and as required by code, Braille must be located 8mm below the bottom line of text (not including descenders).

Braille locator must be used if there are multiple lines of text and characters- horizontally aligned with the first line of braille text.


Construction & Materials

- Materiality Legend**
- | | | |
|------------------------------|----------------------------------|------------------------------|
| C1 | V2 | 01 |
| • C1 finish on 3mm aluminium | • V2 applied on top of aluminium | • Tactile to match C2 finish |
| 02 | | |
| • Braille to match C1 finish | | |

Fixing Details
• Refer to: Section 8, Construction Standards, Typical Wall Mounted Signs




ST.02d
Offences relating to fire exits
Scale 1:2



ST.02e
BCA signage
Scale 1:2



ST.02f
Typical statutory cupboard signage
Scale 1:5



ST.02g
Typical services room signage
Scale 1:5



ST.02h
Triple line services room/statutory cupboard signage
Scale 1:5

Graphic Layout

Offenses & BCA Messaging

FS Millbank Regular
Alignment: Left
Size/ Leading: 8mm, 3.5mm
Tracking: 0+, Optical kerning

Cupboard Messaging

FS Millbank Bold
Alignment: Left
Size/ Leading: 20mm, 10mm
Tracking: 10+, Optical kerning

Construction & Materials

Materiality Legend


- C1

 - C1 finish on 3mm aluminium
- V2


 - V2 applied on top of aluminium

Fixing Details


- Refer to: Section 8, Construction Standards, Typical Wall Mounted Signs




Elevation - FHR Cabinet
Scale: 1:25



Elevation - FHR Door
Scale: 1:25



Elevation - Wall-mounted Extinguisher
Scale: 1:25



Elevation - Wall-mounted FHR
Scale: 1:25

Sign Location

Purpose


To identify room function and or room occupants for BOH utilities relating to fire safety and to meet statutory regulations. Refer to Section 3, Addressing & Terminology, Category 11.

Location


Above or adjacent to a fire hose reel located, extinguisher in a recess, cavity or an obscure location. Signs shall be positioned so as to be clearly visible to persons approaching the fire hose reel location.

Note

- For sign type selection, refer to: Section 5, The Process, Step 3
- For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
- For sign maintenance, refer to: Section 21, Maintenance



Front Elevation - Cantilevered Sign
Scale: 1:25



Front Elevation - Cantilevered Sign
Scale: 1:25

Sign Location

Purpose

To identify cupboard/room function and or room occupants for BOH utilities relating to fire safety and to meet statutory regulations. Refer to Section 3, Addressing & Terminology, Category 11.

Location

Cantilevered sign centred to and 50mm above door frame when fire services and/or equipment are concealed. Signs shall be positioned so as to be clearly visible to persons approaching cupboard location.

Note

- For sign type selection, refer to: Section 5, The Process, Step 3
- For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
- For sign maintenance, refer to: Section 21, Maintenance



ST.03a
Fire Extinguisher
Scale 1:4



ST.03b
Fire Hose Reel
Scale 1:4



ST.03c
Fire Hose Reel and Fire Extinguisher
Scale 1:4



ST.03d
Fire Hose Reel, Fire Hydrant and Fire Extinguisher
Scale 1:4

Graphic Layout

Messaging
FS Millbank Bold
Alignment: Left
Tracking: 10+, Optical kerning

Size
Dependant on sign panel size as shown in diagrams.

Construction & Materials

Materiality Legend

- C1

 - C1 finish on 3mm aluminium
- V2

 - V2 applied on top of aluminium

Fixing Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms



ST.03e
Fire Extinguisher
Scale 1:4



ST.03f
Fire Hose Reel
Scale 1:4



ST.03g
Fire Alarm
Scale 1:4



ST.03h
Firefighting Equipment
Scale 1:4

Graphic Layout

Pictograms
150mm height
Refer to Section 7, Graphic Standards, Pictogram Suite

Dividing Line
Line weight: 1mm

Messaging
FS Millbank Bold
Alignment: Left
Tracking: 10+, Optical kerning


Construction & Materials

Materiality Legend

- | | |
|------------------------------|----------------------------------|
| C3 | V3 |
| • C3 finish on 3mm aluminium | • V3 applied on top of aluminium |

Fixing Details
• Refer to: Section 8, Construction Standards Wall Mounted Signforms

Note
• Pictograms are subject to approval from BCA Consultant to ensure compliance.



Typical Elevation
Scale: 1:25

Sign Location

Purpose



Identifies or provides statutory/ regulatory information.
Refer to Section 3, Addressing & Terminology, Category 11.

Location

Above or adjacent to a fire hose reel located, extinguisher in a recess, cavity or an obscure location. Signs shall be positioned so as to be clearly visible to persons approaching the fire hose reel location.

Note

- For sign type selection, refer to: Section 5, The Process, Step 3
- For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
- For sign maintenance, refer to: Section 21, Maintenance




Graphic Layout

- Messaging**
FS Millbank Bold
Alignment: Left
Tracking: 10+, Optical kerning
- Sizing/ Leading**
Sizing and leading varies per Regulations Family sign type.
- Pictogram**
Single pictogram: 150mm diameter
Double pictogram: 75mm diameter
Refer to Section 7, Graphic Standards, Pictogram Suite

Construction & Materials

- Materiality Legend**
- | | | |
|------------------------------|----------------------------------|--|
| C1 | V2 | V3 |
| • C1 finish on 3mm aluminium | • V2 applied on top of aluminium | • V3 print applied on top of aluminium |
- Fixing Details**
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms





Graphic Layout

- Pictogram**
Single pictogram: 150mm diameter
Double pictogram: 75mm diameter
Refer to Section 7, Graphic Standards, Pictogram Suite
- Dividing Line**
Line weight: 1mm
- Messaging**
FS Millbank Bold
Alignment: Left
Tracking: 10+, Optical kerning
- Sizing/ Leading**
Sizing and leading varies per Regulations Family sign type.

Construction & Materials

- Materiality Legend**
- | | | |
|------------------------------|----------------------------------|--|
| C1 | V2 | V3 |
| • C1 finish on 3mm aluminium | • V2 applied on top of aluminium | • V3 print applied on top of aluminium |
- Fixing Details**
- Refer to: Section 8, Construction Standards, Wall Mounted Signforms




Sign Location


Purpose
Identifies or provides statutory/ regulatory information specific to security.

Location
Applied to solid walls or glazing where appropriate.


- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



ST.05a
Security Warning 100mm
Scale 1:25



ST.05b
Security Warning 200mm
Scale 1:25



ST.05c
Security Warning 300mm
Scale 1:25

Graphic Layout

Messaging
FS Millbank Bold & Regular
Alignment: Left
Tracking: 10+, Optical kerning

Sizing/ Leading
Sizing and leading varies per Security Warning Family sign type.


Pictogram
Single pictogram: 150mm diameter
Double pictogram: 75mm diameter
Refer to Section 7, Graphic Standards, Pictogram Suite

Construction & Materials


Materiality Legend

C1	V2	V3
• C1 finish on 3mm aluminium	• V2 applied on top of aluminium	• V3 print applied on top of aluminium

Fixing Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms



Typical Elevation - Single Sign
Scale: 1:25



Typical Elevation - Double Sign
Scale: 1:25

Sign Location

Purpose



Identifies or provides statutory/ regulatory information for areas that contain hazardous substances or machinery that have immediate physical or chemical effects, such as fire, explosion, corrosion and poisoning, affecting property, the environment or people.

Location

Applied to solid walls or glazing as per statutory requirements.

Note

- For sign type selection, refer to: Section 5, The Process, Step 3
- For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
- For sign maintenance, refer to: Section 21, Maintenance



Graphic Layout


- Pictogram**
Single pictogram: 150mm diameter
Refer to Section 7, Graphic Standards, Pictogram Suite
- Dividing Line**
Line weight: 1mm
- Messaging**
FS Millbank Bold
Size/ Leading: 20mm, 10mm
Alignment: Left
Tracking: 10+, Optical kerning

Construction & Materials

- Materiality Legend**
- C1

V2

V3
- C1 finish on 3mm aluminium
 - V2 applied on top of aluminium
 - V3 print applied on top of aluminium
- Fixing Details**
- Refer to: Section 8, Construction Standards, Wall Mounted Signforms



Graphic Layout

- Pictogram**
Single pictogram: 150mm diameter
Refer to Section 7, Graphic Standards, Pictogram Suite
- Dividing Line**
Line weight: 1mm
- Messaging**
FS Millbank Bold
Size/ Leading: 20mm, 10mm
Alignment: Left
Tracking: 10+, Optical kerning

Construction & Materials

- Materiality Legend**
- C1**

 - C1 finish on 3mm aluminium
- V2**

 - V2 applied on top of aluminium

- Fixing Details**
- Refer to: Section 8, Construction Standards, Wall Mounted Signforms




Graphic Layout

- Pictogram**
Single pictogram: 150mm diameter
Refer to Section 7, Graphic Standards, Pictogram Suite
- Dividing Line**
Line weight: 1mm
- Messaging**
FS Millbank Bold
Size/ Leading: 20mm, 10mm
Alignment: Left
Tracking: 10+, Optical kerning

Construction & Materials


- Materiality Legend**
- | | | |
|------------------------------|----------------------------------|--|
| C1 | V2 | V3 |
| • C1 finish on 3mm aluminium | • V2 applied on top of aluminium | • V3 print applied on top of aluminium |

- Fixing Details**
- Refer to: Section 8, Construction Standards, Wall Mounted Signforms



Elevation - Single full height fixed window or equal width fixed windows. UNSW logo centre aligned to safety decal.

Scale 1:20



Elevation - Fixed windows with varying widths. UNSW logo placed at 1000mm intervals.

Scale 1:20

Sign Location

Purpose


Provide contrast for glazing as per statutory requirements.

Location


On glazed areas walls and doors, as per statutory requirements.

Note


- For sign type selection, refer to: Section 5, The Process, Step 3
- For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
- For sign maintenance, refer to: Section 21, Maintenance



Detail – Yellow
Scale 1:2



Detail – Black
Scale 1:2



Detail – White
Scale 1:2

Graphic Layout

UNSW logo
45mm height


Construction & Materials

Materiality Legend

- V1**
 - Band as digital print V1 finish to self-adhesive film applied to glazing
- V2**
 - Band as black V2 finish self-adhesive film applied to glazing
- V3**
 - Band as white V3 finish self-adhesive film applied to glazing

Fixing Details

- Refer to: Section 8, Construction Standards, Direct Applied Glazing





Typical Elevation
Scale: 1:25

Sign Location

Purpose
Identifies or provides statutory/ regulatory information specific to campus entries and exits

Location
Applied to solid walls, gates, or glazing where appropriate. Signform is to be mounted at the nominated position, or in the same position as existing signage if on a gate.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Graphic Layout

Messaging

FS Millbank Bold & Regular
Alignment: Left
Tracking: 10+, Optical kerning

Sizing/ Leading

Sizing and leading varies per Exit Signage Family
sign type.

Pictogram

Single pictogram: 150mm diameter
Double pictogram: 75mm diameter
Refer to Section 7, Graphic Standards, Pictogram Suite

Construction & Materials

Materiality Legend

- | | | |
|------------------------------|----------------------------------|--|
| C1 | V2 | V3 |
| • C1 finish on 3mm aluminium | • V2 applied on top of aluminium | • V3 print applied on top of aluminium |

Fixing Details

- Refer to: Section 8, Construction Standards, Wall Mounted Signforms

15.0

Temporary & Display Series

This section documents all the temporary and displays signs of the system including specifications for both external and internal signs.

TD.01 Notice Boards: External Large

TD.02 Notice Boards: External Small

TD.03 Notice Boards: Internal Large


TD.04 Notice Boards: Internal Small

TD.05 Notice Boards: Digital

TD.06 A3 & A4 Display Family

TD.07 Temporary Sign

TD.08 Construction Hoarding




Elevation: Cliplok cabinet
Scale 1:20

Sign Location

Purpose
Provides system in an external environment to display information for students and visitors that is updated on a monthly basis.

Location
Applied to solid wall outside teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



01 Detail: LHS
Scale 1:2



02 Detail: RHS
Scale 1:2

Graphic Layout

Messaging
FS Millbank Bold
Size: 20mm
Alignment: Left
Tracking: 10+, Optical kerning


UNSW logo
50mm height

Construction & Materials

Materiality Legend

- | | | |
|------------------------------|----------------------------------|--|
| C2 | V1 | V3 |
| • C2 finish on 3mm aluminium | • V1 applied on top of aluminium | • V3 print applied on top of aluminium |

Construction Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms




Elevation: Tufflok cabinet
Scale 1:20

Sign Location

Purpose
Provides system in an external environment to display information for students and visitors that is updated on a monthly basis.

Location
Applied to solid wall outside teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



01 Detail: LHS
Scale 1:2



02 Detail: RHS
Scale 1:2

Graphic Layout

Messaging
FS Millbank Bold
Size: 20mm
Alignment: Left
Tracking: 10+, Optical kerning

UNSW logo
50mm height

Construction & Materials

Materiality Legend


- C2**

 - C2 finish on 3mm aluminium
- V1**

 - V1 applied on top of aluminium
- V3**

 - V3 print applied on top of aluminium

Construction Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms



Elevation: Vispin noticeboard
Scale 1:20

Sign Location


Purpose
Provides system in an interior environment to display information for students and visitors that is updated on a monthly basis.

Location
Applied to solid wall outside teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



01 Detail: LHS
Scale 1:2



02 Detail: RHS
Scale 1:2

Graphic Layout

Messaging
FS Millbank Bold
Size: 20mm
Alignment: Left
Tracking: 10+, Optical kerning


UNSW logo
50mm height

Construction & Materials

Materiality Legend

- | | | |
|------------------------------|----------------------------------|--|
| C2 | V1 | V3 |
| • C2 finish on 3mm aluminium | • V1 applied on top of aluminium | • V3 print applied on top of aluminium |

Construction Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms



Elevation: Vispin noticeboard
Scale 1:20

Sign Location


Purpose
Provides system in an interior environment to display information for students and visitors that is updated on a monthly basis.

Location
Applied to solid wall outside teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



01 Detail: LHS
Scale 1:2



02 Detail: RHS
Scale 1:2

Graphic Layout

Messaging
FS Millbank Bold
Size: 20mm
Alignment: Left
Tracking: 10+, Optical kerning


UNSW logo
50mm height

Construction & Materials

Materiality Legend

- | | | |
|------------------------------|----------------------------------|--|
| C2 | V1 | V3 |
| • C2 finish on 3mm aluminium | • V1 applied on top of aluminium | • V3 print applied on top of aluminium |

Construction Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms



Elevation: Vispin noticeboard
Scale 1:20

Sign Location


Purpose
Provides digital system to display information for students and visitors that is updated on a monthly basis.

Location
Applied to solid wall outside teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



01 Detail: LHS
Scale 1:2



02 Detail: RHS
Scale 1:2

Graphic Layout

Messaging
FS Millbank Bold
Size: 20mm
Alignment: Left
Tracking: 10+, Optical kerning


UNSW logo
50mm height

Construction & Materials

Materiality Legend

- | | | |
|------------------------------|----------------------------------|--|
| C2 | V1 | V3 |
| • C2 finish on 3mm aluminium | • V1 applied on top of aluminium | • V3 print applied on top of aluminium |

Construction Details
• Refer to: Section 8, Construction Standards, Wall Mounted Signforms



A3 - Elevation
Scale 1:20




A4 - Elevation
Scale 1:20

Sign Location


Purpose
To display A3 and A4 print outs supplied by students and staff.

Location
Applied to solid wall outside teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance




TD.04a - A3 Template Detail
Scale 1:5




TD.04b - A4 Template Detail
Scale 1:5

Construction & Materials

- Specification Note**
- Signlink Avant Garde' aluminium framework 2pack polyurethane painted Dulux Dandelion Yellow A205 Satin 2mm clear acrylic face panel with digital print (30% k) 8mm border to inside face of panel, Apply 8mm magnetic strip tape to affix to assembled framework.
- Construction Details**
- Refer to: Section 8, Construction Standards, Off-the-shelf



Front Elevation
Scale 1:20




Side Elevation
Scale 1:20

Sign Location


Purpose
To display A3 prints out supplied by students or staff for special events.

Location
Freestanding outside buildings with events or at locations where required.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Detail
Scale 1:10



Detail
Scale 1:5

Graphic Layout

- UNSW logo**
150mm height
- Statutory messaging**
FS Millbank Regular
Size/Leading: 10mm, 5mm
Alignment: Left
Tracking: 10+, Optical kerning
- Pictograms**
No Smoking & Dogs on Leash: 25mm diameter

Construction & Materials


Materiality Legend

- | | | |
|--|--|--|
| C1 <ul style="list-style-type: none">C1 finish on 3mm aluminium | V2 <ul style="list-style-type: none">V2 applied on top of aluminium | V3 <ul style="list-style-type: none">V3 print applied on top of aluminium |
| A2 <ul style="list-style-type: none">A2 finish insert | C2 <ul style="list-style-type: none">C2 finish on 3mm aluminium | |


- Construction Details**
 - Refer to: Section 22, Shop Drawings



Elevation - Typical Class A Hoarding
Directional panels to only appear at corner junctions of hoarding
Scale 1:50



Elevation - Typical Mesh Option 1
Colour landscape University logo with yellow background as direct print to hoarding mesh
Scale 1:50




Elevation - Typical Mesh Option 2
Reverse Colour landscape University logo with black background as direct print to hoarding mesh
Scale 1:50


Sign Location

Purpose
Used for construction hoarding to display temporary informational, directional messaging and visual content.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



TD.08a - Elevation Hoarding Print
Scale 1:25



TD.08b -Panel Detail
Scale 1:10

Graphic Layout

Tagline - TD.08a

FS Millbank Bold
Size/ Leading: 130mm, 80mm
Alignment: Left
Tracking: 10+, Optical kerning

Directional Messaging - TD.08b

FS Millbank Regular
Size: 50mm
Alignment: Left
Tracking: 10+, Optical kerning

UNSW logo

240mm height

Construction & Materials

Materiality Legend

- | | | |
|--------------------------------|---|------------------------------------|
| 01 | 02 | V2 |
| • Digital print on canvas mesh | • Coloured coreflute to match UNSW yellow | • Black digital print on coreflute |

Construction Details

- Refer to: Section 22, Shop Drawings

Section

16.0

Environmental Graphics Series

This section documents all the environmental graphics of the system.


EG.01 Privacy Graphic

EG.02 Security Booth Graphics

Correct / Incorrect Graphic Usage



DO: Use artwork as provided in artwork files



DO NOT: Transform aspect ratio horizontally or vertically




DO NOT: Flip or reverse artwork in any orientation


Graphic Application



01 Typical Elevation
Scale 1:25



02 Typical Glazing Section
Scale 1:25



03 Glazing Section Detail
NTS

Notes

Correct Usage

Only use graphic in original form and maintain aspect ratio as per artwork files. Do not stretch, rotate or transform the graphic in any way.

Application

Applied to internal face of glazing to teaching rooms and other places as needed. Graphic and safety decal elements to be cut neatly together with no overlaps and always applied to the same face of glazing.

Note


- For sign type selection, refer to: Section 5, The Process, Step 3
- For content guidelines, refer to: Section 3, Terminology & Addressing
- For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
- For sign maintenance, refer to: Section 21, Maintenance

01

- White print on Avery Dusted glass film

V1

- V1 finish applied to glazing



Elevation - Without frosting
Scale 1:25

Sign Location


Purpose
Provides low visual privacy from outside pedestrian traffic.

Location
Applied to internal face of glazing to teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Detail
Scale 1:10



Full Elevation **Note**
Scale 1:50 White linework shown as magenta.

Construction & Materials


Materiality Legend



- V4 print applied onto glazing

Application Details

- Refer to: Section 8, Construction Standards, Direct Applied Graphics




Elevation - With frosting
Scale 1:25

Sign Location


Purpose
Provides a medium to low visual privacy from outside pedestrian traffic.

Location
Applied to internal face of glazing to teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Detail
Scale 1:10



Full Elevation **Note**
Scale 1:50 White linework and frosting shown as magenta.


Construction & Materials

Materiality Legend

- 01
- White print on Avery
Dusted glass film

Application Details

- Refer to: Section 8, Construction Standards,
Direct Applied Graphics



Elevation - With frosting
Scale 1:25

Sign Location


Purpose
Provides medium visual privacy from outside pedestrian traffic.

Location
Applied to internal face of glazing to teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Detail
Scale 1:10



Full Elevation **Note**
Scale 1:50 White linework and frosting shown as magenta.

Construction & Materials


Materiality Legend



- White print on Avery
Dusted glass film

Application Details

- Refer to: Section 8, Construction Standards,
Direct Applied Graphics



Elevation - With frosting
Scale 1:25

Sign Location


Purpose
Provides high visual privacy from outside pedestrian traffic.

Location
Applied to internal face of glazing to teaching rooms and other places as needed.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Detail
Scale 1:10



Full Elevation **Note**
Scale 1:50 White linework and frosting shown as magenta.

Construction & Materials



Materiality Legend



- White print on Avery
Dusted glass film

Application Details

- Refer to: Section 8, Construction Standards,
Direct Applied Graphics



Sign Location

Purpose
Provides high visual privacy from outside pedestrian traffic along with security booth operational information

Location
Applied to internal face of glazing at security booth.

- Note**
- For sign type selection, refer to: Section 5, The Process, Step 3
 - For content guidelines, refer to: Section 3, Terminology & Addressing
 - For material finishes, refer to: Section 8, Construction Standards, Finishes Schedule
 - For sign maintenance, refer to: Section 21, Maintenance



Detail
Scale 1:5

Construction & Materials

Materiality Legend

- 01

 - Digital print to matte white vinyl
- 02

 - White print on Avery Dusted glass film

Application Details

- Refer to: Section 8, Construction Standards, Direct Applied Graphics

Section 17.0

Specialty Series

This section documents signage that has been designed specifically for particular buildings or areas on campus. The intent is to show these signtypes as examples only.

These signtypes have been designed in consultation with estate management. These designs are exclusively for that specific building and cannot be used outside of that context. If required, please engage with estate management prior to fabrication and installation.


The Chancellery
Celebrating Women Project
Alumni Park Artwork
Morven Brown Student Space Identity
Foosball Tables
Business School

The Chancellery


CH

Drawings are not to scale and are
intended as design reference only.

S1 Level ID
Typical




01 Unfolded Elevation
Level 3 Lift
Scale 1:20



02 Front Detail
Scale 1:5

03 Side Detail
Scale 1:5


Spec
Level number to be fabricated aluminium with 2 pac polyurethane finish to match Dulux 'Vivid White' SW1G1. Signform to be conceal fixed to nominated wall surface with spacer to create 10mm shadow gap and allow for halo illumination. All fixings to be finished to match signform, contractor to advise.



04 Section
Scale 1:2

Note
Drawings are not to scale and are intended as design reference only.

S2.A Room ID
Typical - Overview



01 Typical Elevation
Level 3 Room 308
Scale 1:20


Note
Lettering to be aligned to door opening i.e. if door is on left side, lettering must be left-aligned.

Spec
Lettering to be individually lasercut 5mm thk acrylic letterforms with 2 pac polyurethane finish to match Dulux 'Vivid White' SW1G1. Signform to be adhesive fixed to nominated wall or glazing surface. When placed on glazing, is to be backed with profile-cut white vinyl as shown in 03 Section to conceal adhesive fixings.


Contractor is to produce samples of lettering and display onsite for client review to ensure adequate contrast of white lettering against fluted glass film.

Refer to drawing **UNSW0048U 02 S02 A2** for all setouts.

Note
Drawings are not to scale and are intended as design reference only.




02 Detail
Scale 1:5




03 Side Detail
Scale 1:5

S2.B

Room ID
Boardroom




01 Elevation
Level 3 Boardroom
Scale 1:20



02 Front Detail
Scale 1:2

03 Side Detail
Scale 1:2

Spec
Lettering to be fabricated aluminium with powdercoat finish to match Dulux 'Vivid White' SW1G1. Signform to be conceal fixed to nominated wall surface with spacer to create 10mm shadow gap and allow for halo illumination. All fixings to be finished to match signform, contractor to advise.




04 Section
Scale 1:2

Note
Drawings are not to scale and are intended as design reference only.


S2.C

Room ID
Door Mounted

Note
Drawings are not to scale and are intended as design reference only.



Note
Lettering to be aligned to door opening in all instances
i.e. if door is on left side, lettering must be left-aligned.




04 Detail
Scale 1:5


Spec
Lettering to be individually lasercut 5mm thk acrylic letterforms with 2 pac polyurethane finish, adhesive fixed to nominated door surface.

Finish colour is dependant on door substrate. When placed on timber, signform is to match Dulux 'Vivid White' SW1G1. When placed on plasterboard, signform is to match Dulux 'Stone Grey' 27278126. Contractor is to review all nominated locations on site and provide quantities and setouts in shopdrawing issue.

S2.D Room ID
Panels - Typical




01 Elevation - Ground Floor Meeting Room
Scale 1:20




02 Typical Elevation - North Wing Corridor
Scale 1:20

Spec
Panels as 3mm thk acrylic with 2 pac polyurethane finish to match Dulux 'Vivid White' SW1G1, adhesive fixed to nominated door or wall surface. Messaging to be profile-cut 3M Scotchcal self adhesive vinyl in **Mid Gray 61**. Sign is not to receive clearcoat, to allow for easy future removal and change of vinyl messaging. Contractor is to review all nominated locations on site and provide quantities and setouts in shopdrawing issue.

Note
Drawings are not to scale and are intended as design reference only.




03 Detail - Ground Floor Meeting Room
Scale 1:2



04 Detail - North Wing Corridor
Scale 1:2

S3

Department ID
Ground Floor



01 Elevation
Ground Stair Lobby
Scale 1:20

Note
Signform to be aligned to access control panel as shown, contractor to confirm all dimensions and conditions on site and demonstrate accurate setout in shopdrawings.




02 Detail
Scale 1:5
Spec
Panel as 3mm thk acrylic with 2 pac polyurethane finish to match Dulux 'Vivid White' SW1G1, adhesive fixed to nominated door or wall surface. Graphics and messaging to be profile-cut 3M Scotchcal self adhesive vinyl in **Mid Gray 61** applied to panel surface.


Sign is not to receive clearcoat, to allow for easy future removal and change of vinyl messaging.

Note
Drawings are not to scale and are intended as design reference only.

D1 Level Directory
Typical




01 Unfolded Elevation
Level 3 Lift
Scale 1:20



02 Front Detail
Scale 1:5


Spec
Panel to be 10mm thk MDF with laminate finish to match interiors, with front face as matte white 2-pac polyurethane finish. Signform to be conceal fixed to wall surface with 5mm shadow gap. Graphics and messaging to be profile-cut 3M Scotchcal self adhesive vinyl in **Mid Gray 61** applied to panel surface with clearcoat all over.




03 Side Detail
Scale 1:5

Note
Drawings are not to scale and are intended as design reference only.

D2 Directional
Level 3 Reception



01 Elevation
Level 3 Reception
Scale 1:20





02 Detail
Scale 1:5

03 Side Detail
Scale 1:5

Spec
Panel to be 10mm thk MDF with laminate finish to match interiors, with front face as matte white 2-pac polyurethane finish. Signform to be conceal fixed to wall surface with 5mm shadow gap. Graphics and messaging to be profile-cut 3M Scotchcal self adhesive vinyl in **Mid Gray 61** applied to panel surface with clearcoat all over.


Note
Drawings are not to scale and are intended as design reference only.

01 Statutory Signage
Typical



Note
Drawings are not to scale and are intended as design reference only.

O2.A Amenity ID
Wall Mounted - Typical



01 Typical Elevation
Scale 1:20

Spec
Statutory signform as 5mm thk acrylic with with 2 pac polyurethane finish to match Dulux 'Stone Grey' 27278126, adhesive fixed to nominated wall surface. Sign to conform with BCA section D3.6: Pictograms to be raised 1.0-1.5(h)mm tactile finish in white & Ultramarine Blue (B21 as per AS2700). Tactile lettering to be raised 1.0-1.5(h)mm in white. Tactile letters & pictograms must have rounded edges.

Sign panel edges to have 6mm rounded corners. Entire sign panel, including braille and tactile to be fully encapsulated. Finish of sign to be matte or low sheen. Braille must be Grade 1 Braille in accordance with the criteria set out by the Australian Braille Authority. Contractor to confirm BCA compliance prior to manufacture.

Braille to be same colour as panel, shown indicatively only & content to be checked & typeset by Braille supplier.



02 Detail
Scale 1:2




03 Family
Scale 1:10

Note
Refer to masterplans for all locations and required messaging.


Note
Drawings are not to scale and are intended as design reference only.

O2.B Amenity ID
Pictograms




01 Typical Elevation
Scale 1:20


Spec
Pictograms as 5mm thk lasercut acrylic with 2 pac polyurethane finish to match Dulux 'Vivid White' SW1G1, adhesive fixed to nominated door surface.



Unisex & Accessible



Unisex Ambulant



All Gender

02 Detail
Scale 1:3

Note
Refer to masterplans for all locations and required messaging.

Note
Drawings are not to scale and are intended as design reference only.


The Chancellery – Amenity Identification (Flag)

CH.07c

O2.C

Amenity ID

Flag




01 Front Elevation
Scale 1:20

02 Side Elevation
Scale 1:20


Spec

Signform to be 25mm thk MDF with laminate finish to match interiors, with front and rear face as matte white 2-pac polyurethane finish. Signform to be mechanically concealed fixed to wall surface, contractor to advise. Graphics and messaging to be profile-cut 3M Scotchcal self adhesive vinyl in **Mid Gray 61** applied to both sides of flag with clearcoat all over.



03 Side Detail
Single pictogram
Scale 1:4

04 Front Detail
Scale 1:4



05 Side Detail
Multiple pictograms
Scale 1:4



06 Family
Scale 1:5

Note


Refer to masterplans for all locations and required messaging.

Note

Drawings are not to scale and are intended as design reference only.

O3

Utility ID
Typical



Note
Drawings are not to scale and are intended as design reference only.




Celebrating Women Project

CW

Drawings are not to scale and are intended as design reference only.

ID.04a

Building Identification
Red Centre




01 Elevation
Scale 1:25

Note
Elevation drawn indicatively only, contractor to confirm all dimensions onsite and provide accurate setouts in shopdrawing issue.


Existing building identification (shown on previous page) is to be removed and wall is to be made good prior to installation of new lettering.

Signform to align to top of entry door opening, contractor to confirm on site.



02 Detail
Building ID
Scale 1:10

Spec
Lettering as folded 3mm thk aluminium letterforms with No. 4 linished stainless steel finish. Concealed pin fixing to wall to create 20mm shadow gap, contractor to advise following review of wall surface.. All fixings finished to match letters.




03 Side Detail
Scale 1:10

04 Section
Scale 1:10



05 Detail
Braille Panel
Scale 1:5

Spec
Panel as 10mm thk aluminium with No. 4 linished stainless steel finish, conceal fixed to wall with 5mm shadow gap as shown. Contractor to advise fixing method. Messaging as raised tactile matte black lettering.




06 Side Detail
Scale 1:10

Note
Drawings are not to scale and are intended as design reference only.


ID.04a

Building Identification
Chemical Sciences Building



Note
Elevation drawn indicatively only, contractor to confirm all dimensions onsite and provide accurate setouts in shopdrawing issue. Existing building identification (shown on previous page) is to be removed and concrete wall is to be cleaned and made good prior to installation of new lettering. Any existing regulatory signage is to be relocated, per contractor's onsite review.

Signform to extend to cover any wall damage or fixing holes from previous signform. Contractor to conduct full onsite review and amend sizing accordingly.




Note
Drawings are not to scale and are intended as design reference only.

Celebrating Women – Biography Panel (External)

CW.02a

ID.04b

Building Plaque Chemical Sciences Building



01 Elevation
Scale 1:25

Note
Elevation drawn indicatively only, contractor to confirm all dimensions onsite and provide accurate setouts in shopdrawing issue. Existing sponsor plaque is to be relocated as shown, contractor to ensure concrete wall is cleaned and made good prior to installation of new signage.


Spec
Panel specifications to match messaging panel. Photography as chromaprint direct to panel surface, contractor to advise. Photo shown as placeholder only, UNSW to provide content.



05 Mockup
Scale N/A




07 Spec Reference
Scale N/A



02 Detail Messaging Plaque
Scale 1:5

Spec
Panel as 10mm thk aluminium with No. 4 finished stainless steel finish, conceal fixed to wall with 5mm shadow gap as shown. Contractor to advise fixing method. Messaging as raised tactile matte black lettering **Interpretive text as placeholder only, UNSW to confirm.**




03 Detail Image Plaque
Scale 1:5

04 Side Detail
Scale 1:5

Note
Drawings are not to scale and are intended as design reference only.


ID.20c

Theatre Identification
Biography - Overview




01 Indicative Elevation
Scale 1:20

Note
Elevation drawn indicatively only, contractor to confirm all dimensions onsite and provide accurate setouts in shopdrawing issue. Refer to masterplans for all locations.



05 Detail Heading
Scale 1:5

Spec
Lettering as 5mm thk lasercut aluminium with No. 4 finished stainless steel finish, adhesive fixed to wall surface. Contractor to ensure surface is appropriate for adhesive fixings.



02 Detail Messaging Plaque
Scale 1:5

Spec
Panel as 10mm thk aluminium with No. 4 finished stainless steel finish, conceal fixed to wall with 5mm shadow gap as shown. Contractor to advise fixing method. Typical messaging as etch and fill with matte black paint. Braille to conform with BCA section D3.6: Entire sign panel, including braille messaging to be fully encapsulated. Braille must be Grade 1 Braille in accordance with the criteria set out by the Australian Braille Authority. Contractor to confirm BCA compliance prior to manufacture. Braille to be same colour as panel, shown indicatively only & content to be checked & typeset by Braille supplier.



04 Detail Image Plaque
Scale 1:10


Spec
Panel specifications to match messaging panel. Photography as chromaprint direct to panel surface, contractor to advise.

03 Side Detail
Scale 1:5

Note
Drawings are not to scale and are intended as design reference only.

ID.20a

Theatre Identification
Theatre Name - Typical Lettering



01 Indicative Elevation
Theatre Entry Doors
Scale 1:20

Note
Elevation drawn indicatively only, contractor to confirm all dimensions onsite and provide accurate setouts in shopdrawing issue. Refer to masterplans for all locations.

Lettering is to be right or left aligned depending on orientation of door handle as shown above.
Contractor to confirm all orientations onsite and demonstrate setouts in shopdrawings.



02 Detail
Scale 1:2

Spec
Lettering as 3mm thk lasercut aluminium with No. 4 finished stainless steel finish, adhesive fixed to door surface. Contractor to ensure surface is appropriate for adhesive fixings.

Note
Drawings are not to scale and are intended as design reference only.

G02
Diane
Kell
Theatre

G04
Vũ Nhị-
Thủy
Theatre

104
Patricia
Elizabeth
Mutton
Theatre

105
Galina
Sugowdz
Theatre

G03
Judith
Bullerwell
Theatre


G05
Clara
Patricia
Alfonso
Theatre

G06
Annada
Gohain
Theatre

103
Helen Barry
& Michele
G. Blum
Theatre

03 Messaging Setouts
Scale 1:10

ID.24 Ext. Space Identification
Freestanding Totem




01 Front Elevation
Scale 1:10

Spec
Signform as 10mm thk aluminium panels with matte black two pack polyurethane finish, fixed to internal SHS framing as required. All returns of signform to be 3mm thk aluminium with No. 4 finished stainless steel finish. Contractor to advise on internal construction and structural requirements.


All messaging as matte white raised tactile lettering, images to be chroma-print direct to aluminium panels.

Signform to be mechanically fixed to ground plane with appropriate footings, contractor to advise following onsite review of conditions.


Contractor to provide sample of panel in both matte black and monument matte finish for UNSW review and selection prior to full manufacture.



02 Plan
Scale 1:5



03 Detail
Scale 1:5



04 Section
Scale 1:5


Note
Drawings are not to scale and are intended as design reference only.

Celebrating Women – Trail Signage (Freestanding)

CW.04a

ID.24

Ext. Space Identification Women's Trail - Freestanding Totem




01 Front Elevation
Scale 1:10


Spec
Signform as 10mm thk aluminium panels with matte black two pack polyurethane finish, fixed to internal SHS framing as required. All returns of signform to be 3mm thk aluminium with No. 4 finished stainless steel finish. Contractor to advise on internal construction and structural requirements.

'Celebrating Women' main heading messaging as matte white raised tactile lettering, all other messaging found under key line to be matte white vinyl direct to signform with clearcoat. Images to be chroma-print direct to aluminium panels.


Signform to be mechanically fixed to ground plane with appropriate footings, contractor to advise following onsite review of conditions.



02 Plan
Scale 1:5



03 Detail
Scale 1:5



04 Section
Scale 1:5

Note
Drawings are not to scale and are intended as design reference only.


Celebrating Women – Trail Signage (Wall Mounted)

CW.04a

ID.24

Ext. Space Identification

Women's Trail - Wall Mounted



Note

Drawings are not to scale and are intended as design reference only.

Alumni Park Artwork


AP

Drawings are not to scale and are intended as design reference only.


A1

Alumni Park Artwork Plaque
Ground

Note
Drawings are not to scale and are intended as design reference only.



01 Location Plan
NTS
Note
Plaque to be located on nominated paver tile (shown as magenta), client to confirm.



02 Detail
Scale 1:4
Spec
Artwork plaque to be custom made sandblasted aluminium with messaging as 3mm painted counter relief, entire panel to be surface finished. QR code to be digital print direct to aluminium surface, contractor to advise and ensure longevity of print in outdoor conditions.

Plaque to be fixed to unit paver type PV01 with epoxy resin adhesive, contractor to ensure longevity of fixings in outdoor conditions.


Paver colour shown indicatively only, specification is to match existing on site as shown in 03 Reference Image. Contractor to procure material samples for client review.



03 Reference Image
Scale N/A


A2 Alumni Park Artwork Plaque Bleachers

Note
Drawings are not to scale and are intended as design reference only.



01 Indicative Location
1:20

Note
Signform to be mounted to timber bleachers. Contractor to advise fixing method following review of onsite conditions



02 Location
NTS



03 Detail
Scale 1:4

Spec
Artwork plaque to be 3mm thk aluminium with **Astor Metals Arcturus aged bronze satin finish** (or similar). All messaging as white digital print direct to panel surface.

Contractor to ensure longevity of digital print in outdoor conditions and ensure no fading or blurring.



04 Material Reference
Scale N/A

S1 Interpretive Disc
Overview




01 Detail
Scale 1:1

Spec
Interpretive disc to be 2mm thk aluminium with painted finish to match existing artwork plaque on site (contractor to advise, refer to 03 Reference. All messaging as white digital print direct to panel surface.

Contractor to ensure longevity of digital print in outdoor conditions and ensure no fading or blurring.



03 Spec Reference
Scale N/A




Note
Drawings are not to scale and are intended as design reference only.

Morven Brown Identity

MB

Drawings are not to scale and are intended as design reference only.

Logo



The Study Space logo consists of a white oval background with a brand mark and the 'Study Space' lettering.

The spacing of the brand mark and lettering inside the oval shape should be equal so that the brand mark with lettering are always placed centered within the shape.

The Study Space brand mark and lettering lock-up should not be altered in any way and should not be used without the oval background shape.

Colours

 Study Space Camel	 White
CMYK C 20 M 41 Y 67 K 1	CMYK C 0 M 0 Y 0 K 0
RGB R 204 G 153 B 102	RGB R 255 G 255 B 255
Web #cc9966	Web #ffffff
PMS #cc996	

Colour variation




Main Colourway
To be used in all instances where sufficient contrast is provided

There should be a contrast of at least 30% between the oval white shape and the background it is placed on, to ensure visibility of the white background shape.


For instances where the logo is used on a white or otherwise very light background (i.e. printed material), a diapositive version of the logo can be used which uses a camel coloured oval with white brand mark and lettering.

Please note: this diapositive version is only to be used where absolutely necessary



Diapositive Colourway
To be used in instances where the white oval does not provide sufficient contrast against the background

Study Space Oval





The oval shape should always be placed behind the brand mark and lettering lock-up. This is the primary form of the logo that should appear where possible in both print and signage applications.

In cases where the logo is used on a surface where there is a significant edge or corner in the direct proximity (such as a door or a corner wall), the oval shape can be cut off on one side to accommodate for placement directly on an edge.


The cut off version of the oval shape should only be used where it can be placed directly against an edge. Cutting of the oval shape can only occur on one side of the logo (as shown in the lower images on this page).

The size of the brand mark and lettering lock-up and placement within the cut-off oval has been adjusted to allow for maximum visibility (as shown on this page).

Please note: this page shows the



Study Space Oval



Example: Internal wall with continuous colour on surface


Where the study space logo is used on a large continuous surface, one side of the oval can be cut off on one side and the straight part of the shape can be extended to be applied to fill the surface in order to break up a large space and provide a graphic interlude.

The curved part of the oval should not be extended or altered in any way; only the straight part can be extended.

The cut off edge of the extended oval shape should finish where there is an expressed edge (i.e. edge of a wall, edge of a door) to be aligned with that edge.



Application / Supporting Colours



Example 1: Supporting Colour (terracotta)


When applying the logo to the study space environment, a supporting colour can be used to visually distinguish and give each study space its own character.

This supporting colour can be chosen for use in key signage elements such as vinyl decals, wall colours or signage elements.

The Study Space brand mark and lettering do not change colour and will be applied as camel (as shown throughout this document).

This page shows examples of the Study Space logo applied to typical facade/building signage.

Supporting colours should be chosen in collaboration with the (interior) architect and UNSW management and can be derived from the interior architecture scheme or UNSW branding palette.




Example 2: Supporting Colour (yellow)

Foosball Table Signage

FB

Drawings are not to scale and are intended as design reference only.

O2 Foosball Signage
Typical




01 Side Elevation
Scale 1:10

02 Front Elevation
Scale 1:10

Note
Elevations and all dimensions are indicative only. Contractor to confirm all dimensions and conditions onsite and advise accordingly.




05 Positioning Diagram
Scale N/A



03 Plan Detail
Scale 1:5

Spec
Signform to be formed from 3mm thk aluminium with two pack polyurethane finish to match UNSW Yellow - Dulux 'Dandelion Yellow' A205. Text and logo as digital print direct to substrate.

Signform to be mechanically conceal fixed flush to concrete seating, contractor to advise fixing method.



04 Side Detail
Scale 1:5

Note
Contractor to advise inner structural requirements, and advise on power reticulation to electronic lockboxes.


Note
Drawings are not to scale and are intended as design reference only.

Business School

BS

Drawings are not to scale and are
intended as design reference only.


G1 Glazing Graphic
Zone 1



01 Glazing Partition A
Scale 1:50

Note
Clear backed vinyl applied only to internal glazing panels not to touch glazing frame. Clear back to be made invisible by extending vinyl to full extent of each glazing panel. Contractor to ensure all fixings are concealed. For full graphic refer to UNSWE12-02-G01-07

Note
Drawings are not to scale and are intended as design reference only.



02 Glazing Partition B
Scale 1:50

Note
All messaging as vinyl applied direct to inside face of glazing. UNSW Logo to sit on glazing frame, frame is not to break the graphic. Crest as digital print to vinyl. All messaging to follow a leading line of 1480mm from finish floor level. Safety decal as 3M Opaque graphic film series 7725 in Matte White. For messaging details refer to UNSWE12-02-G01-05


Note
Contractor to provide in-depth shopdrawing analysis of frame depths and widths for each glazing section. UNSW logo subject to change materiality between V1 and F3 Finish and mounting position -internal or external to glazing - depending on conclusions from contractors showdrawing analysis of frame depths and widths.



03 Full Glazing Elevation
Scale 1:200

S1

Room ID
Typical - G23




01 Typical Elevation
Scale 1:20


Note
Safety decal as **3M Opaque graphic film series 7725 in light Grey 121**. 20mm strip above finish in **V1 Finish** direct to glazing.

Safety decal and additional white "leading Line" strip to extend full length of glazing as shown on masterplan.

02 Typical Elevation
Scale 1:20




05 Section
Scale 1:10



03 Room Panel Detail
Scale 1:5

Note
Singform as 3mm thk timber laminate to match architectural finishes. Messaging as profile cut vinyl lettering. Braille 3D printed direct to signform to match **V2 finish**.

All text shown indicatively only and will be confirmed prior to shopdrawing stage.



04 Room Numbering Detail
Scale 1:10

Note
Singform as 3mm thk timber laminate numbers and letters to match architectural finishes. Numbers to be painted **F2 finish**. Vinyl profile cut letters applied to return face of glazing **F1 Finish**. Contractor to ensure all adhesive is concealed.

Note
Drawings are not to scale and are intended as design reference only.

Business School – Entry Wall ID

BS.03

S2

Entry Wall ID


Typical



01 Full Elevation
Scale 1:50

Note

All elevations drawn indicatively dimensions to be confirmed by contractor on site
Laminate panel to be painted matte black panel **P1 Finish.**




02 Plan
Scale 1:20

Note

Plan drawn indicatively angle of wall and all dimensions to be confirmed by contractor on site

5mm thk acrylic white lettering
F3 Finish


Painted matte black substrate
P1 Finish



04 Detail UNSW Logo
Scale 1:10

Note


E3 Finish All logos as digital print to vinyl applied to front face of acrylic returns to match logo edge



03 Detail
Scale 1:10

Note

Messaging as profile cut individual lettering **V2 finish**. Batons as 40mm by 40mm thk acrylic **F3 finish**. All text shown indicatively only and will be confirmed prior to shondrawing stage. Contractor is to allow for full text coverage as text will change



05 Detail Business School Logo
Scale 1:10

Messaging as vinyl
applied direct to
laminate
V2 Finish


White acrylic 40m
40mm thk batons
E3 Finish

10mm thk acrylic
white lettering
A1 Finish

Digital print to vinyl
LINSW logo


Note

Drawings are not to scale and are intended as design reference only.



01 Elevation
Scale 1:20

Note
Signform and messaging to be 100mm from edge left aligned on all faces. Elevation drawn indicatively contractor to check all dimensions on site and to be approved before application. Contractor to ensure all fixings are concealed.



02 Detail
Scale 1:10

Note
Leading lines as 40mm thk acrylic batons F3 Finish. Messaging as profile cut vinyl applied direct to timber laminate. Messaging to be confirmed by client prior to shop drawing phase.



03 Section
Scale 1:10

Note
Drawings are not to scale and are intended as design reference only.

UNSW

For sections 01 - 08, refer to chapter G.1
For sections 09 - 12, refer to chapter G.2
For sections 18 - 23, refer to chapter G.3



UNSW
SYDNEY